

Gunnison Watershed School District Crested Butte Community School Crested Butte, Colorado

Conceptual Budget of Probable Cost 8/19/2022

Improvement Projects

Item No.	Description	Unit	Amount	Cost	Line Total	Category Total	Remarks %
NO.	Description	Unit	Amount	COST	iotai	(Rounded)	Remarks %
1	Site Work					, ,	
2	Sidewalk areas	sf	31,000	\$8.00	\$248,000		0.54%
3	Landscape areas	sf	12,000	\$6.00	\$72,000		0.16%
4	Playground areas	sf	24,000	\$15.00	\$360,000		0.79%
5	Existing elementary parking lot	sf	30000	\$6.00	\$180,000		0.39%
6	Existing HS parking lot	sf	35401	\$10.00	\$354,010		0.77%
7	Existing rear parking lots	sf	16000	\$6.00	\$96,000		0.21%
8 9	Bus drop off lane Entry Drive Realignment	sf sf	5920 22000	\$18.00 \$18.00	\$106,560 \$396,000		0.23% 0.86%
10	Site demolition area	sf	104,000	\$2.00	\$208,000		0.45%
10	Site demonition area	51	104,000	\$2.00	\$200,000		0.45%
11	Sub-total of Site Construction					\$2,020,570	4.41%
12	Building Construction						
13	Interior Renovation Area	sf	20000	\$225.00	\$4.500.000		9.82%
14	Building Additions	sf	41467	\$450.00	\$18,660,150		40.72%
15	Building Mechanical Systems Controls	ls	1	\$245,000.00	\$245,000		0.53%
	Banang moonamoa Oyotomo Controle		•	ΨΣ 10,000.00	Ψ2 10,000		0.33%
16	Sub-total of Building Construction					\$23,405,150	51.1%
17	Deferred Maintenance Scope of Work					\$1,298,200 Includes priorities 1-100 w/base HVAC units	2.8%
18	Direct Cost of Construction					\$26,723,920	58.3%
19	Construction Fees						
20	General Conditions	est.		9%	\$2,405,152.80		5.2%
21	Contractor's Fee	est.		4%	\$1,068,956.80		2.3%
22	Sub-total General Contractor Fees				* - 1, 1,	\$3,474,110	7.6%
23	Indirect Construction Costs						
24	Builder's Risk Insurance:	est.		0.50%	\$150,990.15		0.3%
25	Umbrella & General Liability Insurance:	est.		0.70%	\$211,386.21		0.5%
26	Performance & Payment Bond:	est.		0.90%	\$271,782.27		0.6%
27	Sub-total In-direct Construction Costs					\$634,159	1.4%
28	Cost of Construction					\$30,832,188	67%
29	Escalation Contingency			2	\$3,732,476.46	\$3,732,476.46 2 year of 6% annual escalation anticipated	8.1%
30	Estimating Contingency			10%	\$3,019,802.96	\$3,019,802.96 undefined scope of work	6.6%
31	TOTAL COST OF CONSTRUCTION					\$37,584,468	82%
32	Owner Costs						
33	Logal Sanciago (property agguinition / title work / gorden at any involve	ls			\$30,000		0.1%
33 34	Legal Services (property acquisition / title work / contract review) Owner's Representative Fees	IS IS		1.00%	\$30,000 \$375,845		0.1% 0.8%
34 34	Owner's Construction Contingency	allow		10.00%	\$3,758,447		0.8% 8.2%
J-4	- ·	anow		10.00 /6	ψο, εσο, 44 ε		0.270
25	Design Services - (Arch, civil, landscape, electrical, structural,	054		0.050/	¢2 100 740		6.001
35 36	mechanical) Building Permit (Plan Check Fee):	est. est.		8.25% 0.40%	\$3,100,719 \$150,338		6.8% 0.3%
30	Inspections/ Material Testing/Survey/ Geo-technical /	est.		0.40%	\$ 15U,338		0.3%
37	Environmental:	allow		0.30%	\$112,753		0.2%
38	Mechanical System Commissioning	allow		0.65%	\$244,299		0.5%
39	Furniture Fixtures and Equipment	allow	_	1.25%	\$469,806	assume new furn in new areas of the building	1.0%
40	Subtotal (Owner Costs)					\$8,242,206	18%
	TOTAL DRO JECT BUDGET					\$45.00C.674	
41	TOTAL PROJECT BUDGET 2022 Inflation Factor	oc+		20.00%	\$9,163,586	\$45,826,674 \$54,990,260	100.0%
41	ZOZZ IIIIGIIOTI I GOLOI	est.		20.00%	99, 103,386	\$34,330,£00	