## 3.2 Condition Analysis Matrix

Project: Montrose County School District
Facility: Oak Grove Elementary School (OGES)

2/7/2022

Date of last addition: NA Year round start date:\_\_

Failure Timing Legend 1 The item will fail or has already failed

2 Replace within 5 Years 3 Replace within 6-10 Years (Yellow)

4 Improvement Item

(see scoring tab for details)

Contengency Amount Soft Cost:

					Condition N	Matrix									
						FAIL	FINAL			REMAINING	COST (Direct Cost)	COST (w/ Fees & GC's)	TOTAL COST	TOTAL COST	
ITEM #	FACILITY	LOCATION	ITEM DESCRIPTION	CONSULTANT	ITEM CATEGORY	TIMING	CAT CONSQ RANK		RANK	LIFE (YEARS)	(no soft costs)	(no soft costs)		(w/ contengency)	
1	OGES	INT	Provide vertical grab bars	RTA	Code/ADA	1	5	4	20		\$ 2,800		\$ 3,864		
2	OGES	INT	Provide ADA compliant door signage	RTA	Code/ADA	1	5	4	20		\$ 7,000		\$ 9,660		
3	OGES	INT	Provide ADA compliant toilets	RTA	Code/ADA	1	5	4	20		\$ 33,600		\$ 46,368		
4	OGES	INT	Replace carpeting in 5-10 years	RTA	Flooring System	2	6	3	36		\$ 62,120		\$ 85,726		
5	OGES	INT	Lighting controls	RTA	Lighting System	2	6	6	72		\$ 85,600		\$ 118,128		
6	OGES	INT	Provide privacy curtain in nurse's room	RTA	Code/ADA	1	3	4	12		\$ 1,500	1,725	\$ 2,070		
7	OGES	INT	Provide code compliant handrail and ramp	RTA	Code/ADA	1	5	4	20		\$ 50,000	\$ 57,500	\$ 69,000	\$ 69,000.00	
8	OGES	INT	Provide sprinkler system to 200 wing	RTA	Code/ADA	1	3	4	12		\$ 110,000		\$ 151,800		
9	OGES	INT	Move mirror for visual compliance	RTA	Code/ADA	1	3	4	12		\$ 1,000		\$ 1,380		
10	OGES	INT	Replace windows in bathroom, library, 400 wing and original building	RTA	Window System	1	3	4	12		\$ 35,000		\$ 48,300		
11	OGES	INT	Provide ADA access to stage	RTA	Code/ADA	1	5	4	20		\$ 5,000		\$ 6,900		
12	OGES	EXT	Replace rusted and broken handrail at main entry	RTA	Other	1	4	4	16		\$ 8,000		\$ 11,040		
13	OGES	EXT	Replace front entry stairs that are deteriorating from freeze and thaw	RTA	Pavement System	1	1	1	1		\$ 8,000		\$ 11,040		
14	OGES	EXT	Replace wooden eaves that have dry rot	RTA	Roofing System	2	2	3	12		\$ 10,860	12,489	\$ 14,987		
15	OGES	EXT	Replace Bell tower wood that looks to have dry rot	RTA	Roofing System	3	7	3	63		\$ 8,500	9,775	\$ 11,730	\$ 11,730.00	
16	OGES	EXT	Consult with a restoration specialist for exterior brick	RTA	Other	2	7	3	42		\$ 31,400	\$ 36,110	\$ 43,332	\$ 43,332.00	
17	OGES	EXT	Replace windows in overhangs	RTA	Window System	1	7	6	42		\$ 10,000	11,500	\$ 13,800	\$ 13,800.00	
18	OGES	EXT	Replace deteriorated plaster at south stairs and retaining wall to basement	RTA	Other	1	7	3	21		\$ 10,000	\$ 11,500	\$ 13,800	\$ 13,800.00	
19	OGES	EXT	Replace deteriorated foundation stone	RTA	Other	1	7	3	21		\$ 100,000	115,000	\$ 138,000	\$ 138,000.00	
20	OGES	EXT	Replace leaking gutters	RTA	Roofing System	1	2	3	6		\$ 5,792		\$ 7,993		
21	OGES	EXT	Provide roofs snow guards at exit doors of classrooms	RTA	Roofing System	1	1	1	1		\$ 3,000	3,450	\$ 4,140	\$ 4,140.00	
22	OGES	EXT	Reroute downspout at front entry that drains into parking lot	RTA	Roofing System	1	1	1	1		\$ 8,000	9,200	\$ 11,040	\$ 11,040.00	
23	OGES	EXT	Eliminate Ice build-up at the bus loop	RTA	Pavement System	1	1	1	1		\$ 16,000	\$ 18,400	\$ 22,080	\$ 22,080.00	
24	OGES	EXT	Replace single pane steel windows	RTA	Window System	1	7	5	35			\$ -	\$ -	\$ -	
25	OGES	EXT	Replace existing main entry wood frame and single pane glazing	RTA	Window System	1	7	5	35		\$ 5,140	5,911	\$ 7,093	\$ 7,093.20	
26	OGES	EXT	Replace exterior wood that has rotted and deteriorated	RTA	Other	2	7	3	42		\$ 20,000	23,000	\$ 27,600	\$ 27,600.00	
27	OGES	EXT	Replace deterioration brick and mortar at the base of the exterior walls	RTA	Other	2	7	3	42			\$ -	\$ -	\$ -	
28	OGES	EXT	Regrade around the building, grade is higher than floor level	RTA	Pavement System	1	7	6	42		\$ 10,000		\$ 13,800		
29	OGES	EXT	Provide gutters at the north elevation low sloped roof	RTA	Roofing System	1	1	3	3		\$ 1,200		\$ 1,656		
30	OGES	EXT	Replace rotten wood on multi-colored wall at north of gym	RTA	Other	1	7	3	21		\$ 10,000	11,500	\$ 13,800		
31	OGES	EXT	Reroute downspout that drains into play patio causing ice hazard on west	RTA	Roofing System	1	1	1	1		\$ 8,000	9,200	\$ 11,040	\$ 11,040.00	
32	OGES	EXT	Reroute North downspout drains onto same patio	RTA	Roofing System	1	1	1	1		\$ 8,000		\$ 11,040		
33	OGES	EXT	Replace rusted metal doors and frames	RTA	Other	3	7	6	126		\$ 30,000		\$ 41,400		
34	OGES	EXT	Replace deteriorated precast panels	RTA	Other	3	7	6	126		\$ 50,000		\$ 69,000		
35	OGES	PORT	Replace rotting ADA ramp	RTA	Code/ADA	2	5	4	40		\$ 40,643	3 \$ 46,739	\$ 56,087		
36	OGES	PORT	Replace deteriorated ceiling tiles	RTA	Other	2	6	5	60		\$ 14,400		\$ 19,872		
37	OGES	PORT	Replace carpet that has reached the end of its life	RTA	Flooring System	1	6	6	36		\$ 9,400		\$ 12,972		
38	OGES	PORT	No plumbing in either portable (drinking water or restrooms)	RTA	Potable Water System	1	4	5	20		\$ 65,000	\$ 74,750	\$ 89,700	\$ 89,700.00	

_	_										_	_	_
39	OGES		Mechanical system:  1. Original stone building: Two, packaged, heating and cooling units on the ground. One on west side and one on east side. Ductwork in basement. Units date to 2005.  2. 1974 building: Three, packaged, heating and cooling rooftop units utilizing existing ductwork. Units date to 2005.  3. 2005 Addition: Six, packaged, heating and cooling rooftop units. Units date to 2005.  4. Gym: One, packaged, heating and cooling unit on the ground on the west side. Exposed ductwork in gym. Unit dates to 2005.  All units are Lennox. All units are at end of published lifetimes and should be considered for replacement in the next 5 years.  3, 10-ton; 4, 12.5-ton; 3, 15-ton; 1, 8.5-ton; 1, 6-ton; 1, 7.5-ton.	Bighorn	HVAC System	2	6	3	36	\$ 661,500	\$ 760,725	\$ 912,870	\$ 912,870.00
40	OGES		The BAS is a Trane SC controller located in the 2005 addition connected the SD's Ensemble campus wide system. This dates to the McKinstry project in 2013. The lastest version of software should be installed.	Bighorn	HVAC System	2	6	7	84	\$ 5,000	\$ 5,750	\$ 6,900	\$ 6,900.00
41	OGES	2005 Addition	There is a wet fire sprinkler system in the 2005 addition and the corridor to the old gym. The fire riser is in the 1974 building on the NE side. The backflow preventer for domestic water is located in this room also. No upgrades anticipated.	Bighorn	Other	4	11	8	352		\$ -	\$ -	\$ -
42	OGES	Basement	There is a sewage ejector basin/pump in the basement of the original building that dates to 2005. No upgrades anticipated.	Bighorn	Other	4	11	7	308	\$ 85,500	\$ 98,325	\$ 117,990	\$ 117,990.00
43	OGES	Site	There is a sewage grinder/basin to the west of the school that was installed in 2019. No upgrades anticipated.	Bighorn	Other	4	11	7	308	\$ 123,500	\$ 142,025	\$ 170,430	\$ 170,430.00
44	OGES	Building wide	Plumbing fixtures are a mix of newer (2005) and older units. Fixtures are functional and their condition is consistent with age and use. No upgrades anticipated.	Bighorn	Other	3	11	7	231	\$ 85,920	\$ 98,808	\$ 118,570	\$ 118,569.60
45	OGES	Site	Natural gas derives from a master meter on the south side of the 2005 addition. Gas is piped underground to several locations with risers and regulators. No upgrades anticipated.	Bighorn	Other	4	11	8	352	\$ 78,375	\$ 90,131	\$ 108,158	\$ 108,157.50
46	OGES	Kitchen	There is a Type I hood in the kitchen with Ansul fire protection. There is an evap cooler used for makeup air. The reach in coolers do not have proper clearance for airflow/cooling. There was an incident where the evap cooler was left on to cool the coolers and the outside air caused a frozen water line and attendant damage. The ventilation system for the kitchen and coolers should be replaced. This would include new hood, grease fan, makeup air unit with gas heat and evaporative cooling, and Ansul fire protection.	Bighorn	HVAC System	2	2	3	12	\$ 163,300	\$ 187,795	\$ 225,354	\$ 225,354.00
47	OGES	Building wide	There are a number of water heaters in the school. The kitchen uses an on demand Rinnai located in a closet off the kitchen. No upgrades are anticipated.	Bighorn	Potable Water System	3	11	7	231	\$ 72,000	\$ 82,800	\$ 99,360	\$ 99,360.00
48	OGES	Electrical Room	Main service @ 1600 amps. Date of manufacture 2003. The service was new in 2004 along with new addition; this also upgraded several panels throughout.	Bighorn	Electrical Power System	4	11	3	132	\$ 80,000	\$ 92,000	\$ 110,400	\$ 110,400.00
49	OGES	Distribution panels throughout		Bighorn	Electrical Power System	4	7	6	168	\$ 9,000	\$ 10,350	\$ 12,420	\$ 12,420.00
50	OGES	Main Building corridors and	The corridors and classrooms have fluorescent lighting and dual level switching. During the walk about it was noticed that several classrooms have covering over the lenses. I asked about the reasoning and was informed that several students were affected by the strobing effect of fluorescent lights and the coverings helped. If LED lighting was installed throughout the idea of strobing would be eleminated and in addition 90% of the LED lights come with the ability to be dimmable. Installing LED lighting would in addition to helping with the ill effects of fluorescent lights would also help with the energy usage as well. If the lighting fixtures are replaced the lighting control system needs to be considered.	Bighorn	Lighting System	2	4	4	32	\$ 183,480	\$ 211,002	\$ 253,202	\$ 253,202.40
51	OGES	IT Room	The main data switch in the IT room needs to have labeling and an indicator of the area served for each cable and use cable managing systems to unclutter the cabling	Bighorn	Other	4	9	3	108	\$ 32,528	\$ 37,407	\$ 44,889	\$ 44,888.64
52	OGES	Building Entry Security	The School District uses local access control. This means that each door has a badge swipe or keyed entry. It would be more advantageous if there was a "head end" campus wide access control system.	Bighorn	Security Alarm System	4	9	3	108	\$ 35,000	\$ 40,250	\$ 48,300	\$ 48,300.00
	1	1				l				I			

	1		When originally installed the fire clarm system was adequate; since that								1				
		Building	When originally installed the fire alarm system was adequate; since that time there has been a push in schools to have voice evacuation. This												
53	OGES	Fire Alarm System	system could be amended to have that capability with the correct modules.	Bighorn	Fire Alarm System	4	6	4	96	\$ 34,240	\$ 39,376	\$	47,251	\$	47,251.20
54	OGES	North	North Parking East lot (8987sq. ft.)	Delmont	Pavement System	2	6	6	72	\$ 89,870	\$ 103,351	•	124,021	Ф	124,020.60
55	OGES	North	North Parking Last lot (3507sq. it.)  North Parking West lot (13502 sq. ft.)	Delmont	Pavement System	3	6	6	108	\$ 135,020			186,328		186,327.60
56	OGES	East	East Parking lot (22400sq.ft.)	Delmont	Pavement System	2	2	6	24	\$ 201,600			278,208		278,208.00
57	OGES	East	Bus Loop sidewalk (2056sq.ft.)	Delmont	Concrete System	2	2	6	24	\$ 14,392			19,861		19,860.96
58	OGES	East	East of building (Drainage)	Delmont	Other	2	2	6	24	\$ 20,000			27,600		27,600.00
59	OGES	Kitchen	Reach in cooler and freezer units appear to be in good condition, but show signs of wear and age. No obvious issues observed or relayed.	Other	Other	2	9	7	126	\$ 40,000			55,200		55,200.00
60	OGES	Kitchen	The dish washing area includes a dish machine and spray rinse are included in the equipment. Dish machine showing signs of wear and age. No obvious issues observed or relayed.	Other	Other	2	9	7	126	\$ 20,000	\$ 23,000	\$	27,600	\$	27,600.00
61	OGES	Kitchen	Recommend adding a vegetable prep sink.	Other	Other	1	3	1	3	\$ 8,000	\$ 9,200	\$	11,040	\$	11,040.00
62	OGES	Kitchen	3 compartment sink does not have 2 each, 24" drain boards.	Other	Other	1	3	1	3	\$ 8,000			11,040		11,040.00
63	OGES	Kitchen	Exhaust hoods with fire suppression. Hood and fire suppression should be replaced.	Other	Other	2	3	7	42	\$ 50,000	\$ 57,500	\$	69,000	\$	69,000.00
64	OGES	Kitchen	Recommend steamer be relocated to main kitchen and placed below exhaust hood.	Other	Other	3	9	7	189	\$ 1,000			1,380		1,380.00
65	OGES	Kitchen	Serving line, no obvious issues observed or relayed	Other	Other	4	9	7	252	\$ 20,000			27,600		27,600.00
66	OGES	Kitchen	Recommend replacing wood tables, with stainless steel tables.	Other	Other	1	3	3	9	\$ 2,000			2,760		2,760.00
67	OGES	Kitchen	Mixers, recommend replacement with current models, which include all safety devices.	Other	Other	1	1	1	1	\$ 6,000			8,280	\$	8,280.00
68	OGES	EXT	The Gym roof is failing and in need of repair. This roof is slated for replacement and repair in a project planned for this year.	Other	Roofing System	1	2	3	6	\$ 235,000	\$ 270,250	\$	324,300	\$	324,300.00
											_	_	_		

<u> </u>								<u> </u>			
I	Condition		Totals Totals				Totals	Grand Totals			
I	0-25	\$	1,166,044	\$	1,340,951	\$	1,609,141	\$	1,609,141		
I	26-50	\$	1,083,683	\$	1,246,236	\$	1,495,483	\$	1,495,483		
I	51-100	\$	237,610	\$	273,252	\$	327,902	\$	327,902		
I	> 100	\$	897,843	\$	1,032,519	\$	1,239,023	\$	1,239,023		
I	Totals ->	\$	3,385,180	\$	3,892,957	\$	4,671,549	\$	4,671,549		